

Sample quote

Description	Qty	Per	Price	Total
PAVING REMOVAL				
Removal of existing pavers as required for new works.	47.00	m2	42.53	1,998.68
				1,998.68
EXCAVATION				
Excavate to reduce levels (hand); sandy loam. Material to be carted to existing soil pile on site.	3.00	m3	341.99	1,025.96
				1,025.96
BRICK EDGING				
Installation of 2 course brick edging as detailed on landscape plan. (Clients existing pavers to be used)	12.00	m	28.25	338.94
				338.94
BRICK ON EDGE GARDEN EDGING				
Brick garden edging; cement mortar joints (10mm); commons - 76mm wide. (Clients existing pavers to be used)	14.00	m	21.10	295.47
				295.47
SANDSTONE PAVING PREPARATION				
Removal of existing sandstone flagging and preparation of area as required for new flagging	12.00	m2	81.77	981.29
				981.29
SANDSTONE PAVING				
Sandstone paving;sawn;50mm thick irregular shape	12.00	m2	158.42	1,901.09
				1,901.09
GARDEN BED SOIL				
Import and spread garden bed soil;hand;100mm thick	18.00	m2	16.32	293.71
				293.71
TURF				
Supply and installation of 75mm turf underlay base and thereafter supply and installation of Matilda soft leaf Buffalo turf	36.00	m2	33.26	1,197.50
				1,197.50

Sample quote

Description	Qty	Per	Price	Total
MULCH				
Mulching; spread over site by hand;70mm depth; Forest fines	18.00	m2	13.85	249.29
				249.29
PLANTINGS				
Supply and installation of 200 mm pot size Hydrangea macrophylla	10.00	no	26.08	260.82
Supply and installation of 200 mm pot size Carissa 'Desert Star'	12.00	no	25.03	300.38
Supply and installation of 140 mm pot size Ajuga 'Catlins Giant'	12.00	no	16.63	199.58
Supply and installation of 200 mm pot size Asparagus meyerii	5.00	no	25.03	125.16
Supply and installation of 305 mm pot size Dracena marginata ' Multi stemmed'	1.00	no	156.98	156.98
				1,042.92
HERB / VEGETABLE BOX				
Supply and installation of a herb / vegetable box as located on the landscape plan inclusive of selected plants	1.00	no	250.59	250.59
				250.59
CARPENTRY BIN SCREEN				
Wall slats;1700mm high x 2200mm long;Merbau;140 x 25mm @ 10mm	27.20	m	14.97	407.26
Support posts Merbau; spaces 0.75 metre centres: 90 x 90 mm posts 1700 high	6.90	m	51.26	353.70
				760.97
STUMP GRINDING				
Grinding out of palm stump near pool and stump roots in paving area	3.00	h	173.25	519.75
				519.75
SUBTOTAL				10,856.15
GST				1,085.61
TOTAL				11,941.76